BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT54201

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/18/2022-23, Date: 04-11-2022

Name of Work:Supply and Erection of Sign Boards in ward no. 09 Amruthahalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of HARSHITH RAJ L R (SUNSHINE INFRASTRUCTURES)	
				In Figures	In Words
1	12.96	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. In all kinds of soils Depth upto 1.5 m	Cum	150.0	Rupees One Hundred Fifty Only
2	87.12	Direction and Place Identification Signs with size more than 0.9 m2 size Board: Providing and erecting direction and place identification retro reflectorised sign as per IRC:67:2012 made of high intensity grade sheeting vide clause 801.3, fixed over aluminium sheeting, 2 mm thick or Aluminium composite material sheet with overall thickness of 4mm with area exceeding 0.9 m2 fixed over back support frame of min 40 x 40 x 5mm angle mounted on a mild steel circular pipe 65 NB, firmly fixed to the ground by means of properly designed foundation with M25 grade cement concrete 45 x 45 x 60 cm, 60 cm below ground level as per approved drawing Providing and erecting overhead signs with a corrosion resistant 2mm thick aluminium alloy sheet reflectorised with high intensity retro-reflective sheeting as per IRC:67:2012 with vertical and lateral clearance given in clause 802.2 and 802.3 and installed as per clause 802.7 over a designed support system of aluminium alloy or galvanised steel trestles and trusses of sections and type as per structural design requirements and approved plans	Sqm	7100.0	Rupees Seven Thousand One Hundred Only
3	124.8	Providing and applying two coats of ready mix paint of approved brand on steel surface after thorough cleaning of surface to give an even shade	Sqm	90.0	Rupees Ninety Only
4	720	Lettering with black Japan paint of approved brand and manufacture to give an even shade including preparing the surface after thoroughly cleaning the surface to remove all dirt, dust and foreign matter, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge	Cms	1.5	Rupees One and Fifty Paise Only

Harshith RJ LR

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

ಕಾರ್ಯ ಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬೃ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು